BRUHATH BANGALORE MAHANAGARA PALIKE,

Office of the Executive Engineer Dasarahalli Division

Schedule-B

NAME OF WORK: Construction of concrete roads and other works at Shettyhalli colony roads in ward no 12, Shettyhalli sub Division

Sl. No	Description of work	Unit	Qty	Sanctioned rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	732.94	211.79	Rupees Two hundred eleven and seventy nine paise only
2	Providing, laying, spreading and compacting cushed Cum stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	314.12	2001.28	Rupees Two thousand one and twenty eight paise only
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	314.12	5421.90	Rupees Five thousand four hundred twenty one and ninety paise only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike
Dasarahalli Division, Bengaluru

Scanned by CamScanner

4	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 Its conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). &= Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, soparation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine Cum aggregate 0.46 etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	313.39	5210.96	Rupees Five thousand two hundred ten and ninety six paise only
5	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	2094.10	72.08	Rupees Seventy two and eight paise only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Executive Engineer
Dasarahalli Division
Bruhat Bengaluru Mahanagara Palike,
Dasarahalli Division, Bengaluru-57

Scanned by CamScanner